



# STT Delhi 1

## Factsheet

Operational since 2014, STT Delhi 1 at VSB Bangla Sahib is preferred by cloud service providers, network service providers and enterprise customers. It is incorporated with direct fiber paths and connectivity thus offering greater control and lower risks. It follows all design principles of resiliency, no single point of failure, concurring maintainability and lots of other such features that meet with all TIA 942 requirements.

### Building Overview

- Operational since 2004
- Location: Bangla Sahib, Delhi
- Gross Area: ~4,500 sq. ft.
- Total Power Capacity: ~ 0.94MW of IT load
- Customer SLA for availability: up to 99.982
- Slab-to-slab Height: 5 m
- Floor Loading: 1200 Kg/metre square
- Loading Bay: 1 No.
- Passenger Lift: 1360 Kg. - 2 Nos
- Freight Lift: 3000 Kg. - 1 Nos

Located in close proximity to an ISP network POP

### Other features & Certifications

- ISO 14001
- TL 9000



## Security

- Multi-layers 24/7 security system
- State-of-the-art fire protection & suppression system (NOVEC based Supression System)
- High-level physical security, biometric access management
- Carrier Neutral, Multiple fiber pass, all leading network service providers onsite



## Cooling

- CRAC: PAC
- CRAC: DX machines
- Precision air conditioners: N + N



## Power

- Dedicated 2 feeders of 11 KV supply from different substations.
- N+1 generator system
- UPS: N+N
- UPS Power Distribution: N + N
- Fuel Distribution 24 hours at full load

## STT Global Data Centres India Private Limited

C/o Tata Communications Ltd., Tower B, 5th Floor, Plot No. C 21 & C36, G Block, Bandra Kurla Complex,  
Vidyanagari Post, Bandra East, Mumbai - 400098

**W:** [sttelemediagdc.com/in-en](http://sttelemediagdc.com/in-en)

**E:** [marketing@sttelemediagdc.in](mailto:marketing@sttelemediagdc.in)